

CERTIFIED LAND CORNER RESTORATION

Index No. Z-11

State of Wisconsin }  
County of Lan glade } ss.

I Anthony B. Kiedrowski, do hereby certify that on the 15<sup>th</sup> day of February, 1978, I found evidence of the S<sup>3</sup>/<sub>4</sub> corner of 33 Township 31, North, Range 9, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

.....  
.....  
.....

History of original corner establishment:

June, 1851, James Marsh set a wood post for the original corner.  
June, 1937, D.A. Hintz set a 3" iron pipe with a brass cap.


Description of corner evidence found:

The existing 3" iron pipe that was found was determined to be 100 feet out of sequence by computation of a closed traverse. The distance to the SW corner of Section 33 is 2747.38' and the distance to the SE corner of Section 33 is 2547.37', therefore this monument was disregarded in the computing of the standard parallel. The new monument was set on the true line at a proportionate distance between adjacent existing corners.


Description of monument and accessories I established to perpetuate the original location of this corner

SET 2"X44" IRON PIPE.

SEE REVERSE SIDE.



○ = Corner monument restored.



Dated at Wisc. Rapids, Wis., this 21st day of February, 1978.

Signature Anthony B. Kiedrowski Title R.L.S. Registration No. 878  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19..... at..... o'clock..... M.

.....  
(Register of Deeds)

By..... Deputy

FORM 965 R. C. MILLER CO., MILWAUKEE

43109330000

43109330020

Ties are to nail and discs driven into trees.

