

CERTIFIED LAND CORNER RESTORATION

31-13

Index No. R-7

State of Wisconsin }  
County of Lan glade } ss.

I Raymond J. Hallisy, do hereby certify that on the 19th day of April, 1969, I found evidence of the N 1/4 Corner corner of Section 29 Township 31 N, North, Range 13 E, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Max Johnson

History of original corner establishment:

Corner set by M. Hutchinson on October 21, 1909  
Square 6" post scribed 1 1/4  
B.T Tamarack 8" N 58 1/4° W 49 3/4 lks

Description of corner evidence found:



Square post as set by Hutchinson. Top in fair shape - Point in excellent shape  
Also B.T. as described but now about 12" in diameter  
Faced old B.T. at breast height with



Description of monument and accessories I established to perpetuate the original location of this corner.

New corner: 2" iron pipe with brass cap marked N 1/4 Sec 29 T31N R13E

- B.T.s 1 Tamarack 8" S 11° E 16ft. 10in.
- 2 Tamarack 8" N 58° W 9ft. 8in.
- 3 Tamarack 7" N 70° E 23ft.



○ = Corner monument restored.

Dated at Antigo, Wis., this 21 day of April, 1969

Signature Raymond J. Hallisy Title Reg. Land Surveyor Registration No. S-685  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of \_\_\_\_\_, I hereby certify that the within instrument was filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_ at \_\_\_\_\_ o'clock \_\_\_\_\_ M.

(Register of Deeds)

By \_\_\_\_\_ Deputy

12