

PLAT OF SURVEY

PART OF GOVERNMENT LOT 1 OF SECTION 16, T30N-R12E, TOWN OF NORWOOD, LANGLADE COUNTY, WISCONSIN

THE WEST 1/2 OF PARCEL #016-0252.009 IS DESCRIBED AS FOLLOWS:

Commencing at the South 1/4 Corner of Section 16; Thence S88°29'22"E, along the South line of Government Lot 1 of said Section, 1360.59 feet; Thence S88°15'58"E, 66.65 feet to the Point of Beginning; Thence N06°24'00"E, 86.35 feet to a meander corner which lies S06°24'00"W, 8 feet more or less from the approximate ordinary high water mark of Moose Lake; Thence S82°52'51"E, along a meander line, 37.01 feet to a meander corner which lies \$10°15'16"W, 11 feet more or less from the approximate ordinary high water mark of said lake; Thence S10°15'16"W, 83.51 feet; Thence N88°15'58"W, 31.50 feet to the Point of Beginning.

THE EAST 1/2 OF PARCEL #016-0252.009 IS DESCRIBED AS FOLLOWS:


Commencing at the South 1/4 Corner of Section 16; Thence S88°29'22"E, along the South line of Government Lot 1 of said Section, 1360.59 feet: Thence S88°15'58"E. 98.15 feet to the Point of Beginning; Thence N10°15'16"E, 83.51 feet to a meander corner which lies S10°15'16"W, 11 feet more or less from the approximate ordinary high water mark of Moose Lake; Thence S82°52'51"E, along a meander line, 37.01 feet to a meander corner which lies S14°21'35"W, 5 feet more or less from the approximate ordinary high water mark of said lake; Thence S14°21'35"W, 81.08 feet; Thence N88°15'58"W, 31.50 feet to the Point of Beginning.

I. Timothy J. Rusch, Professional Land Surveyor, do hereby certify:

That I have surveyed and mapped by the order of Marvin Ecker, a part of Government Lot 1 of Section 16, T30N-R12E.

That this survey was for the purpose of locating property boundaries only. Other geographical features were not mapped.

That this is a true and correct representation of the boundaries surveyed to the best of my knowledge and belief.



SURVEYED BY: RUSCH ENGINEERING & SURVEYING LLC **400 RUSCH ROAD ANTIGO, WI 54409** (715)623-5044 PROJECT #17-5707 FIELDWORK COMPLETED 06/02/2017